

[Validate](#)[Print](#)[Help](#)**Item Rate BoQ**

Tender Inviting Authority: Hindu College, University of Delhi

Name of Work:Re-erection of Principal Bungalow, Hindu College, Delhi University

Contract No: HC-1/39

Name of the Bidder/ Bidding Firm / Company :	
--	--

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
<b>1</b>	<b>Part I- CIVIL AND PLUMBING WORKS</b>					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m. as directed by Engineer-in-charge.All kinds of soil.	80	Cum		0.00	INR Zero Only
2	Excavating trenches of required width for pipe, cables etc including excavation for sockets ,& dressing of sides ,ramming of bottoms ,for all depth including getting out the d soil,& then returning the soil as required, in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming ,watering, etc and disposing of surplus excavated soil as directed, within lead of 50m. All kinds of soil. Pipes, cables etc exceeding 80 mm dia but not exceeding 300 mm dia	180	Mtr		0.00	INR Zero Only
3	Providing and laying in position cement concrete of specified grade INcluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	90	cum		0.00	INR Zero Only
4.01	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	10	sqm		0.00	INR Zero Only
4.02	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	35	sqm		0.00	INR Zero Only
4.03	Suspended floors, roofs, landings, balconies and access platform	356	sqm		0.00	INR Zero Only
4.04	Shelves (Cast in situ)	10	sqm		0.00	INR Zero Only
4.05	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	644	sqm		0.00	INR Zero Only
4.06	Columns, Pillars, Piers, Abutments, Posts and Struts	181	sqm		0.00	INR Zero Only
4.07	Stairs, (excluding landings) except spiral-staircases.	15	sqm		0.00	INR Zero Only
4.08	Edges of slabs and breaks in floors and walls	66	Meter		0.00	INR Zero Only

5	Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentering at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured). Suspended floors, roofs, landing, beams and balconies (Plan area to be measured)	397.04	sqm		0.00	INR Zero Only
6	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars.	6000	kilogram		0.00	INR Zero Only
7	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto floor V level Thermo-Mechanically Treated bars	16950	kilogram		0.00	INR Zero Only
8	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/recoverable separately)					
8.01	All works upto plinth level	40	cum		0.00	INR Zero Only
8.02	All works above plinth level upto floor V level	113	cum		0.00	INR Zero Only
9	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	70	cum		0.00	INR Zero Only
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	209	cum		0.00	INR Zero Only
11	Half brick masonry with F.P.S. bricks of class designation 75 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	143	sqm		0.00	INR Zero Only
12	Extra for providing and placing in position 2 Nos. 6mm dia. M.S. bars at every third course of half brick masonry (with F.P.S. bricks).	143	sqm		0.00	INR Zero Only
13	Providing and fixing 18mm thick gang saw cut mirror polished pre moulded and prepolished) machine cut for flooring, staircase treads , riers and landings, kitchen platforms, vanity counters, window sills , facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab upto 0.50 sqm	8	sqm		0.00	INR Zero Only
14	Providing and fixing machine cut, mirror/ eggshell polished , Marble stone work for wall lining (veneer work) including dado, skirting, risers of steps etc., in required design and pattern wherever required, stones of different inished surface texture, on 12 mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of atching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the Engineer-in-Charge. 18 mm thick Italian Marble stone slab Perlato Rosso verona Fire Red or Dark Emperadore etc	101.6	sqm		0.00	INR Zero Only

15	Providing and fixing IS:3564 marked having brand logo with ISI embossed on the plate door weight 36 KG to 80 KG and door width from 701 mm to 1000 mm aluminium extruded section body tubular type universal hydraulic door closer with double speed adjustment with necessary accessories and screws etc.complete	22	each		0.00	INR Zero Only
16	Providing and fixing 50cm long aluminium kicking plate 100x3.15 mm anodised (anodic coating not less than grade AC 10 as per IS :1868) transparent or dyed to required colour or shade with necessary screws etc. complete.	6	each		0.00	INR Zero Only
17	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 12 mm uPVC or aluminium powder coated U beading	177.38	sqm		0.00	INR Zero Only
18	Extra for providing frosted glass panes 5 mm thick instead of ordinary float glass panes 5 mm thick in doors, windows and clerestory window shutters. (Area of opening for glass panes excluding portion inside rebate shall be measured).	55	sqm		0.00	INR Zero Only
19	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame, sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. Profile of frame shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid eparately).Note: For uPVC frame, sash and mullion extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Casement cum fixed panel window having both end single casement panel, middle fixed panels and at top completelyfixed ventilator with S.S friction hinges (350 x 19 x 1.9) made of (big series) frame 67 x 60 mm , sash 67 x 80 mm & mullion 67 x 80 mm all having wall thickness of 2.3 ± 0.2 mm and single glazing bead/double glazing bead of appropriate dimension. (Area of window - ANY)	127	sqm		0.00	INR Zero Only

<b>20</b>	Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick alvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealent over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealent shall be paid separately) Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Three track three panels sliding window with fly proof S.S wire mesh (Two nos. glazed & one no. wire mesh panels) made of (big series) frame 116 x 45 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of window above 1.75 sqm).	77.77	sqm		0.00	INR Zero Only
<b>21</b>	Providing and fixing SS 304 sliding door bolts, including all necessary screws et.					
<b>21.01</b>	600x16	4	each		0.00	INR Zero Only
<b>21.02</b>	450x16	34	each		0.00	INR Zero Only
<b>21.03</b>	300x16 mm	3	each		0.00	INR Zero Only
<b>21.04</b>	250x16 mm	17	each		0.00	INR Zero Only
<b>22</b>	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1962.75	kg		0.00	INR Zero Only
<b>23</b>	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	928	kg		0.00	INR Zero Only
<b>24</b>	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1200	kg		0.00	INR Zero Only
<b>25</b>	Providing and fixing stainless steel ( Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	250	kg		0.00	INR Zero Only
<b>26</b>	Providing & fixing glass panes with putty and glazing clips in upvc windows, windows, clerestory windows, all complete with : 5 mm thick glass panes	204.78	sqm		0.00	INR Zero Only

27	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm Thick	20	sqm		0.00	INR Zero Only
28	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	18	sqm		0.00	INR Zero Only
29	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand), including pointing with cement mortar 1:2 (1 cement : 2 stone dust) with an admixture of pigment to match the shade of stone. Red sand stone	34.95	sqm		0.00	INR Zero Only
30	Extra for Kota stone/ sand stone in treads of steps and risers using single length up to 1.5 metre .	18	sqm		0.00	INR Zero Only
31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of size 600 mm x 300 mm or as decided / approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade all complete as per the directions of Engineer-in-charge.	153.45	sqm		0.00	INR Zero Only
32	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	1	Cum		0.00	INR Zero Only
33	Providing and fixing panelled or panelled and glazed shutters for doors, windows	28	sqm		0.00	INR Zero Only
34	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	18	sqm		0.00	INR Zero Only
35	providing and fixing heavy duty ball bearing Butt hinges Brand Name : Dorset - Size : 127 x 76 x 3 inch alongwith necessary screws	60	each		0.00	INR Zero Only
36	Providing and fixing door lever handle brand Dorset product name Cornus	30	each		0.00	INR Zero Only
37	Providing and fixing lever handle with mortice lock dorset make New antic model 8inch havey plate 6x4 hardness lock body with havey cylinder combo pack	8	each		0.00	INR Zero Only
38	Providing and fixing door stopper HAFELE Stainless Steel Wall Mounted Door Stopper 72 mm with Screw Cover (Screws Not Seen)	14	each		0.00	INR Zero Only
39	Providing and fixing Hettich Door Closer with Standard arm, Fire rated, HSA 10 F: EN 2/3/4 Item code: 9227816 HSA 10 D EN: EN 2/3/4 Rack And Pinion (Symmetric) Mechanism Door Closer Finish : Silver	2	each		0.00	INR Zero Only
40	Providing and laying rectified Glazed Ceramic floor tiles of size 600 mm x 600 mm or as decided / approved by Engineer-in-charge (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. all complete.	29	sqm		0.00	INR Zero Only

41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete 11.41.4 Size of Tile 1000x1000 mm	133	sqm		0.00	INR Zero Only
42	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab jet Black, Cherry Red, Elite brown, Cat Eye or equivalent.	522.86	sqm		0.00	INR Zero Only
43	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	8	rmt		0.00	INR Zero Only
44	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.					
44.01	Single tee without door 110x110x110 mm	8	each		0.00	INR Zero Only
44.02	Bend 87.5° 110 mm bend	16	each		0.00	INR Zero Only
45	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	300	sqm		0.00	INR Zero Only
46	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	429.16	sqm		0.00	INR Zero Only
47	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade Two or more coats on new work	1246.29	sqm		0.00	INR Zero Only
48	Finishing walls with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr / 10 sqm	38	sqm		0.00	INR Zero Only
49	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work on steel surface	345	Sqm		0.00	INR Zero Only
50	Polishing wooden surface with melamine polish after sanding with sand paper no. 180 , then 320, then applying 2 coats of wood tech epoxy insulator then dent filling with wood tech filler then staining wood tech wood stains interiors by spraying . Then applying wood tech Melamyne coating of Asian paints brand	80.5	sqm		0.00	INR Zero Only
51	Providing and laying Vimzinc standing seam system using Quartz Zin type sheeting with specified purlins of cold bend z section 200x80x20x2.5 items complete with all accessories, nuts , screws, cleats , plates etc.	107.1	sqm		0.00	INR Zero Only
52	Providing , filling and levelling in floor with Autoclaved aerated Cement ( AAC ) blocks	5.38	Cum		0.00	INR Zero Only
53	Providing and applying 12 mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite/ perlite respectively conforming to IS: 2547 (Part - 1 & II) 1976, applied on hacked / uneven background such as bare brick/ block/ RCC work on walls & ceiling at all floors and locations, finished in smooth line and level etc. complete.	1246.29	sqm		0.00	INR Zero Only

54	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 20 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints ( 10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer in- charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	81.6	Cum		0.00	INR Zero Only
55	Extra for providing and mixing hardening compound of approved quality as per manufacturer's specification in cement concrete.	2502.4	Litre		0.00	INR Zero Only
56	Providing and laying in position bitumen hot sealing compound for expansion joints etc. 16.46.1 Using grade 'A' sealing compound. per cm	272	depth per cm width per m length		0.00	INR Zero Only
57	Providing and fixing water closets Jaquar company Florentine series Code :FLS-WHT-5953UFMS Description : Rimless Wall Hung WC with UF soft close slim seat cover, Hinges and all Accessories Size:360x545x380mm . Item includes all accessories, all type of piping,white cement, sundries , brackets etc. Complete	5	each		0.00	INR Zero Only
58	Providing and fixing Jaquar Wash Basin Aria ARS WHT 39903 Type:Table Top Colour:White Shape:Rectangle Dimensions:700 x 435 x 135 mm Item includes all accessories, piping, white cement, sundries , brackets etc. Complete	6	each		0.00	INR Zero Only
59	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia	7	each		0.00	INR Zero Only
60	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	5	each		0.00	INR Zero Only
61	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge . concealed work including cutting chases and making good the walls etc.					
61.01	20 mm nominal outer dia .Pipes.	160	metre		0.00	INR Zero Only
61.02	25 mm nominal outer dia .Pipes.	252	metre		0.00	INR Zero Only
61.03	32 mm nominal outer dia .Pipes.	63	meter		0.00	INR Zero Only
62	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. Circular tank	6000	Per liter		0.00	INR Zero Only
63	Providing and fixing C.P. brass Single Lever Basin Mixer Jaquar brand exposed part Range :Aria Code :ARI-CHR-39233NK Description :Exposed Part Kit of Single Lever Basin Mixer Wall Mounted Consisting of Operating Lever, Cartridge Sleeve, Wall Flange, Nipple & Spout (Compatible with ALD-233N & ALD-235N)	7	each		0.00	INR Zero Only

64	Providing and fixing C.P. brass Single Lever Basin Mixer Jaquar brand concealed part Allied Code :ALD-CHR-233N Description :Concealed Body for Single Lever Basin Mixer Wall Mounted. But without Exposed Parts	7	each		0.00	INR Zero Only
65	Providing and fixing C.P. brass Bib Cock Jaquar brand Range :Aria Code :ARI-CHR-39037 Description :Bib Cock with Wall Flange	3	each		0.00	INR Zero Only
66	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of Jaquar brand Angle Valve with Wall Flange PRODUCT CODE: ARI-CHR-39053 PRODUCT RANGE: ARIA	35	each		0.00	INR Zero Only
67	Providing and fixing health faucet ( hand shower ) Jaquar brand Range :Allied Code :ALD-CHR-573 Description :Hand Shower (Health Faucet) with 8mm Dia 1.2 Meter Long Flexible Tube and Wall Hook	5	each		0.00	INR Zero Only
68	Providing and fixing exposed part of Divertor mixer Jaquar brand Model:ARI 39065K Type Of Mounting:Wall Mounted Type of Mixer:Manual No. Of Connections:2.0 Connection Possible To:Spout,Overhead Shower,Hand Shower,Body Shower Description:Single Lever Exposed Parts Kit of Divertor Consisting of Operating Lever, Wall Flange (with seals) & Button Only (Suitable for Item ALD-065)	4	each		0.00	INR Zero Only
69	Concealed Body for Single Lever Diverter 40mm Cartridge Range :Allied Code :ALD-CHR-065N Description :Concealed Body for Single Lever Diverter 40mm Cartridge with Button Assembly, Cartridge Sleeve (Button On Top) But without Exposed Parts	4	each		0.00	INR Zero Only
70	Providing and fixing Jaquar Round Shape Multi Flow Hand Shower HSHCHR1939 by Jaquar Features Product Type : Overhead Shower Size : 100 mm Finish : Chrome Shape : Round Material : ABS. The item to be executed inclusive of all types of piping and allied parts.	4	each		0.00	INR Zero Only
71	Providing and fixing Jaquar brand Overhead Shower Range :Rain Showers Code :OHS-CHR-35497 Description :Overhead Shower 200X200mm Square Shape Single Flow (ABS Body Chrome Plated with Gray Face Plate) with Rubit Cleaning System. The item to be executed completely inclusive of all types of piping and allied parts.	4	each		0.00	INR Zero Only
72	Jaquar Concealed Flush Tank JCS WHT 2400WS Brand Jaquar Model JCS WHT 2400WS Finish White Type Of Installation Concealed Type Of Mounting Wall Mounted Type of Frame Half Frame Flush Type Mechanical Suitable For Wall Hung WC Description Single piece slim concealed cistern with wall mounting frame, installation kit and "S-Type" drain pipe connection set for inclusive of wall hung WC of flush control plate The item to be executed completely inclusive of all types of connecting piping and allied parts.	5	each		0.00	INR Zero Only
73	Providing and fixing Jaquar Artize Soap Dish Holder Brass Chrome Plated Range :Kubix Prime Code :AKP-CHR-35731P Description :Soap Dish Holder	6	each		0.00	INR Zero Only
74	Providing and fixing Jaquar Towel Rack Hotelier Series AHS 1581H Jaquar Model AHS 1581H Location of Use Shower Area Series Hotelier Finish Chrome COMBINED DIMENSIONS 600 x 250 mm Model Fin Code AHS-CHR-1581H DESCRIPTION Towel Rack With Lower Hanger (Stainless Steel) With Hook	6	each		0.00	INR Zero Only
75	PROVIDING AND FIXING Jaquar Towel Ring Square Continental Series ACN 1121N Brand Jaquar Model ACN 1121N Location of Use Basin Series Continental Finish Chrome COMBINED DIMENSIONS 210 x 210 mm Model Fin Code ACN-CHR-1121N DESCRIPTION Towel Ring Square With Round Flange	6	each		0.00	INR Zero Only



76	Providing and fixing square-mouth S.W. gully trap class SP1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design : 150 x 100 mm size P type. With sewer bricks conforming to IS : 4885	6	each		0.00	INR Zero Only
77	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :250 mm dia. R.C.C. pipe	30	meter		0.00	INR Zero Only
78	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making	6	each		0.00	INR Zero Only
79	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design :0.91 m deep with S.F.R.C. cover and frame heavy duty, HD-20 grade designation) 560 mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, foot rests and 12mm thick cement plaster at the external surface shall be paid for separately) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1	each		0.00	INR Zero Only
80	Constructing brick masonry road gully chamber 50x45x60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design : bricks in cement mortar 1:4 (1 cement : 4 coarse sand ) with precast R.C.C. vertical grating complete as per standard design : 19.28.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	6	each		0.00	INR Zero Only

<b>81</b>	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand ) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineerin-Charge : With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	407.74	Sqm		<b>0.00</b>	INR Zero Only
<b>82</b>	Providing and fixing soil, waste and vent pipes in uPVC SWR pipings including all fittings with or without doors . Only length is to be measured from GT , Manhole to Cowl or fittings. 110 mm dia	73	meter		<b>0.00</b>	INR Zero Only
<b>83</b>	Providing and Fixing Delhi quartz stone cladding of approved quality approximately in 9"x9"x4" stone sizes in approved irregular pattern with around 10 mm th. Grooves laid with 1:4 Cement , badarpur/coarse sand mortar , with recessed pointing in 1:2 Cement sand mortar in approved design. The work shall be done as per approved sample and any deviation shall have to be rectified at the risk and cost of the contractor. The cladding shall be done on the walls , in floors and on steps	156	Sqm		<b>0.00</b>	INR Zero Only
<b>84</b>	P/F CPVC union approved make CPVC pipes i/c cutting and making all complete as per the directions of Engineer-in-charge.					
<b>84.01</b>	25 mm nominal bore	1	mtr		<b>0.00</b>	INR Zero Only
<b>84.02</b>	32 mm nominal bore	1	mtr		<b>0.00</b>	INR Zero Only
<b>85</b>	P/F CPVC ball valve (gate valve) of approved make in CPVC pipes i/c cutting and making all complete as per the directions of Engineer-in-charge.					
<b>85.01</b>	25 mm nominal bore	1	each		<b>0.00</b>	INR Zero Only
<b>85.02</b>	32mm nominal bore	1	each		<b>0.00</b>	INR Zero Only
<b>86</b>	Providing and fixing uplasticised PVC connection pipe with brass unions : 45 cm length and 15 mm nominal bore	5	each		<b>0.00</b>	INR Zero Only
<b>87</b>	Providing and fixing CP Grating Square Grating, Size: 5" X 5"SS304 Brand Onida Shape Square Material Stainless Steel Size 5" x 5"/6" x 6" Cat No 60/3025 Model No 5120/5121 125 mm nominal dia with 25 mm waste hole/without hole	7	each		<b>0.00</b>	INR Zero Only
<b>88</b>	Extra for lapatto finish Granite in lieu of polished granite in item 11.56	522.86	sqm		<b>0.00</b>	INR Zero Only

89	Extra for using Double beam screed vibrator , Vacuum dewatering using suction mat ,filter pads and vacuum pump ,floater and power trowelling as per manufacturer's specification for item no. 16.43.2 to achieve smooth VDF flooring.	1348	sqm		0.00	INR Zero Only
90	Extra for providing 8 mm th float glass in place of 5 mm th glass in Item 34	204.78	sqm		0.00	INR Zero Only
91	Extra for providing 3-4mm Grout joint in tiles with letcrete epoxy grout	405.45	sqm		0.00	INR Zero Only
92	Extra for providing and finishing superior exposed brick work with recessed pointing as in existing Girls hostel as per approval	167.23	Cum		0.00	INR Zero Only
93	Extra for using shuttering ply in the soffits of slabs in addition to Item 4 c	356	sqm		0.00	INR Zero Only
93.01	<b>PART – II ELECTRICAL WORK</b>					
94	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FR PVC insulated copper conductor single core cable etc. as required. Group C	80	Point		0.00	INR Zero Only
95	Wiring for twin control light point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface /recessed medium class PVC conduit, 2 way modular switch,modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc as required	12	Point		0.00	INR Zero Only
96	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required					
96.01	3 x 1.5 sq.mm	110	Meter		0.00	INR Zero Only
96.02	6 x 1.5 sq.mm	56	Meter		0.00	INR Zero Only
96.03	9 x 1.5 sq.mm	35	Meter		0.00	INR Zero Only
96.04	3 x 2.5 sq.mm	50	Meter		0.00	INR Zero Only
96.05	6 x 2.5 sq.mm	90	Meter		0.00	INR Zero Only
96.06	3 x 4 sq.mm	90	Meter		0.00	INR Zero Only
96.07	6 x 4 sq.mm	90	Meter		0.00	INR Zero Only
96.08	3 x 6 sq.mm	100	Meter		0.00	INR Zero Only
97	Supplying and drawing following pair, 0.5 sq.mm FR PVC insulated copper conductor, unarmoured telephone cable in the existing surface/ recessed steel/ PVC conduit as required					
97.01	2 Pair	50	Metre		0.00	INR Zero Only
97.02	4 Pair	45	Meter		0.00	INR Zero Only
98	Supplying and drawing co-axial TV cable RG-6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/ recessed steel/ PVC conduit as required.	50	Meter		0.00	INR Zero Only
99	Supplying and fixing of following sizes of medium classPVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
99.01	20mm	345	Metre		0.00	INR Zero Only
99.02	25 mm	234	Metre		0.00	INR Zero Only
99.03	32 mm	30	Meter		0.00	INR Zero Only

<b>100</b>	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
<b>100.01</b>	15/16 amp switch	39	each		<b>0.00</b>	INR Zero Only
<b>100.02</b>	6 pin 15/16 amp socket outlet	18	each		<b>0.00</b>	INR Zero Only
<b>100.03</b>	Telephone socket outlet	12	each		<b>0.00</b>	INR Zero Only
<b>100.04</b>	TV antenna socket outlet	8	Each		<b>0.00</b>	INR Zero Only
<b>100.05</b>	Bell Push	5	Each		<b>0.00</b>	INR Zero Only
<b>101</b>	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required	15	Each		<b>0.00</b>	INR Zero Only
<b>102</b>	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.					
<b>102.01</b>	1 or 2 Module (75mm x 75mm)	15	Each		<b>0.00</b>	INR Zero Only
<b>102.02</b>	8 Module (125mm x 125mm)	18	Each		<b>0.00</b>	INR Zero Only
<b>102.03</b>	12 Module (200mm x 150mm)	16	Each		<b>0.00</b>	INR Zero Only
<b>103</b>	Supplying and fixing following Modular base & cover on existing modular metal box etc. as required					
<b>103.01</b>	1 or 2 Module	15	Each		<b>0.00</b>	INR Zero Only
<b>103.02</b>	8 Module	18	Each		<b>0.00</b>	INR Zero Only
<b>103.03</b>	12 Module	16	Each		<b>0.00</b>	INR Zero Only
<b>104</b>	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden bolock including connection etc. as required.	11	Each		<b>0.00</b>	INR Zero Only
<b>105</b>	Erection of wall bracket /ceiling fittings of all sizes and shapes containing upto two GLS lamps per fitting, complete with all accessories including connection etc. as required.	62	Each		<b>0.00</b>	INR Zero Only
<b>106</b>	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube etc. directly on ceiling/ wall, including connection with 1.5 sq.mm FR PVC insulated, copper conductor, single core cable and earthing etc. as required.	12	Each		<b>0.00</b>	INR Zero Only
<b>107</b>	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq.mm FR PVC insulated, copper conductor, single core cable etc. as required.	15	Each		<b>0.00</b>	INR Zero Only
<b>108</b>	Installation of exhaust fan upto 450 mm sweep in the existing opening, including making the hole to suit the size of the above fan, making good the damage, connection, testing, commissioning etc. as required.( Up to 450mm sweep)	6	Each		<b>0.00</b>	INR Zero Only
<b>109</b>	Extra for fixing the louvers/ shutters complete with frame for a exhaust fan of all sizes.	6	Each		<b>0.00</b>	INR Zero Only
<b>110</b>	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper busbar, neutral busbar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 2+12 way, Double door	1	Each		<b>0.00</b>	INR Zero Only
<b>111</b>	Supplying and fixing following way, prewired, TP&N MCB distribution board, of steel sheet for 415 volts, on surface/ recess, complete with loose wire box, terminal connectors for all incoming and outgoing circuit, duly prewired with suitable size FR PVC insulated copper conductor up to terminal blocks, tinned copper busbar, neutral link, earth bar, din bar, detachable gland plate, interconnection, powder painted including earthing etc. as required. (But without MCB/RCCB/ Isolator).					
<b>111.02</b>	8 Way (4+24),Double Door.	2	Each		<b>0.00</b>	INR Zero Only

<b>111.03</b>	12 Way (4+36) Double Door	1	Each		0.00	INR Zero Only
<b>112</b>	Supplying and fixing 5 amps or 32 amps rating, 240 volts, 'B' series, miniature circuit breaker suitable for lighting and other load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	8	Each		0.00	INR Zero Only
<b>113</b>	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 40 amps	1	Each		0.00	INR Zero Only
<b>114</b>	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps	1	Each		0.00	INR Zero Only
<b>115</b>	Earthing with G.I. earth pipe 4.5 mtr long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with without charcoal/coke and salt as required.	2	Set		0.00	INR Zero Only
<b>116</b>	Earthing with copper Earth plate 600mmx600mmx3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/coke and salt as reqd.	2	Set		0.00	INR Zero Only
<b>117</b>	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required	12	Mtr		0.00	INR Zero Only
<b>118</b>	Providing and fixing 6 SWG dia G.I wire on surface or in recess for loop earthing along with existing surface / recessed conduit / submain wiring / cable as required.	12	Mtr		0.00	INR Zero Only
<b>119</b>	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 35 sq. mm and upto 95 sq. mm	83	Meter		0.00	INR Zero Only
<b>120</b>	Supplying of following sizes PVC insulated and PVC sheathed power cable of 1.1 KV grade armoured L.T cable as required conforming to IS:1554/IS-7098 ( Part-I ) 1998 as reqd at site. 4C x 25 Sq.mm Aluminium armoured	295	Meter		0.00	INR Zero Only
<b>121</b>	Supplying and drawing co- axial TV cable RG-11 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/recessed steel/PVC conduit as required.	120	Meter		0.00	INR Zero Only
<b>122</b>	Supply and fixing modular type A/C box complete with 16amp socket outlet 6 to 32 amp SPMCB, cover plate, connection testing and fixing etc as reqd	15	Each		0.00	INR Zero Only
<b>123</b>	Supply of Wall mounted MIRROR Luminaire suitable for 1 x 15 watt LED lamp complete as required. ( Philips make ) cat no. FMS 200/111	28	Each		0.00	INR Zero Only
<b>124</b>	Supply of BULKHEAD Luminaire with toughened frosted glass suitable for 1 no 9 watt LED complete as required. ( Philips make ) cat no	12	Each		0.00	INR Zero Only
<b>125</b>	Supply and fixing Led Down light 12 Watt including all fittings (Make:-Philips/Bajaj/Wipro)	56	Each		0.00	INR Zero Only
<b>126</b>	Supply of following size of A.C. exhaust fan Size of 300 mm, 900RPM single phase heavy duty complete with motor, blade fan and cover complete accessories in all respect. (Make:- Khaitan/Bajaj/Usha)	7	Each		0.00	INR Zero Only
<b>127</b>	Supply of 1200mm sweep A.C electric ceiling fan, capacitor type double ball bearing complete with 300mm down rod. Canopies, shackles, blades, but without regulator suitable for operation on 230/240 volts, 50Hz, single phase, A.C. supply etc as reqd. (Make:-Bajaj/Usha/Khaitan)	15	Each		0.00	INR Zero Only
<b>128</b>	Supply and fixing RJ-45 Computer jack socket for computer LAN point on the existing with modular plate and switch box including connection and testing in all respect at site.	8	Each		0.00	INR Zero Only

129	Supply and drawing of following size Cat-06 cable FR PVC insulated copper conductor LAN Cat-06 cable in the existing surface/recess steel/PVC conduit as regd.	120	Meter		0.00	INR Zero Only
130	Supplying, installation, testing & commissioning of Aircooled Split Air-conditioners each comprising an outdoor unit consisting of Rotary Compressor, Condensor fan,etc. with outer casing and indoor Hi-wall Type 1.5 TR unit consisting of blower, filter, motoretc. having specified CFM 230+/-10% ,1-50 Hz alongwith cordless remote, (R-22) 1.5 TR with BEE 4 star rating.	8	Each		0.00	INR Zero Only
131	Supplying, installation, testing & commissioning of Aircooled ceiling concealed Air-conditioners each comprising an outdoor unit consisting of Rotary Compressor, Condensor fan,etc. with outer casing and indoor ceiling concealed type 2.0 TR unit consisting of blower, filter, motoretc. having specified CFM 630+/-10% ,1-50 Hz alongwith cordless remote, (R-22 refrigerant) 2.0 TR with BEE 4 star rating.	4	Each		0.00	INR Zero Only
132	Installation charges for 1.5 TR Hi-wall type Airconditioner	8	Each		0.00	INR Zero Only
133	installation charges for 2.0 TR Ceiling concealed type Airconditioner	4	Each		0.00	INR Zero Only
134	Soft Copper Pipe 1/2"& 1/4" having thickness of .8 mm for 1.5 TR AC units	90	Rmtr		0.00	INR Zero Only
135	Soft Copper Pipe 1/2"& 3/4" having thickness of 1.0 mm for 2.0 TR AC units	25	Rmtr		0.00	INR Zero Only
136	4 c (1.5mm) electrical wiring from indoor to outdoor unit (BIS)	90	Rmtr		0.00	INR Zero Only
137	3 c (2.5 sqmm) Electrical wiring from MCB to outdoor units (BIS)	90	Rmtr		0.00	INR Zero Only
138	6 sq mm Electrical wiring from MCB to outdoor units as / BIS	180	Rmtr		0.00	INR Zero Only
139	25 mm Dia. Hard PVC drain pipe	230	Rmtr		0.00	INR Zero Only
140	Voltage stabilizers 4 KVA for A/C	12	Each		0.00	INR Zero Only
141	M.S. angle stand for outdoor units	12	Each		0.00	INR Zero Only
142	Supply and fixing of Gyeaser/ water heater 25 Ltrs capicity complete as read (Make:-Hevells - WB025 or eqivalent Recold/Smith)	6	Nos		0.00	INR Zero Only
143	Supply installation testing and commissioning R.O.water purifier (Kent Grand 8 L RO + UV +UF Water Purifier (White)	2	Each		0.00	INR Zero Only
144	Supplying, installing, testing & commissioning of Domestic Water Lifting Pumps to feed Overhead Tank. (1HP) including all fittings as per direction of Engineer-in-charge. Location - Near underground water tank Part III Miscellaneous	1	each		0.00	INR Zero Only
145	<b>Filling and compaction with Construction debris available at the College within 500 m Lead.</b>	140	Cum		0.00	INR Zero Only
146	If there are any extra items which are not covered in items given above they shall be paid at a fixed percentage below or above DSR 2018 as per the percentage decided in the beginning. Please quote the net percentage rate here . For example if the contractor wants to quote 5% below DSR 2018 please fill .95 . So that amount shall become Rs. 9,50,000.0	1000000	Percentage to be filled in points		0.00	INR Zero Only
<b>Total in Figures</b>					<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>					<b>INR Zero Only</b>	